

Maintenance

XG Control (radioactivity icon)

Control: 45 kV and 66 mA (20 kV and 10 mA in idle status)

Raise the voltage first.

Lower the intensity first.

- 66 → 60; steps of 10 (15-20 s for each step)
- 45 → 40; steps of 10 (idem)

(It takes a couple of minutes in total)

Scripts: Aging/Start script to restart Short takes 31 min. After that you should wait 1-2h for a stable beam

No need to shut down if it's for less than a week

To shut down, first go to idle status (20 kV, 10 mA), then X-rays OFF, and stop vacuum after Check if Chiller/Target are also off after in the Main

For RESTART

- CHILLER
- PUMP(VACUUM)
- X-RAYS

[7.6E-5 (Pa) Vacuum level] [140 Bias] electronic force applied on the beam Don't change the filament current FC 6.6 V Change the bias for each new filament to reach the FC of 6.6 V

When it has just restarted: Stay in idle (20 kV, 10 mA) overnight if it was down for several weeks; only 1-2h if it was down a few hours.

Water flow and Temperature FLOW/TARGET 9.6 FLOW2TUBE 4.3-4.2

From:

<https://bsi.inscog.eu/> - **BSI wiki**

Permanent link:

<https://bsi.inscog.eu/doku.php?id=crystallography:collection:frx:maintenance&rev=1468317335>

Last update: **2023/11/01 20:17**

